

No.	Type	Name of the Project/Tender	Brief Scope of Work	Location of the Project	Planned start & finish Dates
1	Construction	P 7317 : Riser protectors installation in UAD & P7283 : Cellar & Main Deck Extension	Install new riser protectors on 10 wellhead platforms (WHPT-03/11/13/14/16/19 to 23) in order to provide protection against boat impact on the riser. The detailed design engineering to be carried out by ZADCO and material procurement & installation by contractor using ZADCO hired M/V Barracuda for offshore works. To construct deck extension for new offices and modification in existing mechanical workshop at Umm Al Dalkh CPC.	Umm Al Dalkh	Planned Award : Q3 2009 Finish : Q3 2011
2	Construction	Service area sub station upgrade	Engineering, procurement, construction & commissioning for new electrical room, modification of existing 6.6 kv SWBD (schneider electric make) and removal of existing 250 kva transformer, supply / installation of new 1250 kva transformer, 6 / 10kv cable, LV power and control cables, 380v - 2000a LV SWBD, outgoing cabling, earthing and lighting work.	Zirku island - service area	Planned Award : Q3 2009 Finish : Q4 2011
3	Construction	Upgradation of amenities centre (renovation works)	Overall area of amenities centre - 10,000 sq.mtr. 1. Replacement of false ceiling and lighting fixtures and wall & floor tiles in all toilets. 2. Interior design & supply of furniture. 3. Insulation replacement of hvac ducting & chilled water piping system	Zirku island - amenities centre	Planned Award : Q3 2009 Finish : Q4 2011
4	Construction	Fiber Optic Cabling For Zirku Island	Supply And Installation Of Fiber Optic Cabling System, Together With 4 - Fiber Optic Patch Panels. Estimated Length Of Fibre Optic Cable 25 Km.	Zirku island - plant and accommodation areas, A & B.	Planned Award : Q2 2009 Finish : Q1 2011
5	Consultancy	P 8341 : Power System Adequacy Study	Due to the planned upgrade of upper Zakum production, a study is planned to be performed during 2009 to establish adequacy of the existing system and resulting upgrade, followed by conceptual design for the same.	Upper Zakum	Planned Award : Q4 2009 Finish : Q4 2010
6	EPC	P7218 STFFD	Full field development including New facilities at Zirku Island, modifications to 6 WHPTs & new Pipelines connecting WHPTs to PMP & Island.	SATAH	Planned Award : Q2 2011 Finish : Q3 2013
7	Procurement & Construction	P8316 Slot extension	Procurement & Installation of Topside modifications on 17 WHPTs as part of 750K Production Build up.	Upper Zakum	Planned award : Q4 2009 Finish : Q3 2012

No.	Type	Name of the Project/Tender	Brief Scope of Work	Location of the Project	Planned start & finish Dates
8	Procurement & Construction	P8276 / P8224	Topside modifications on existing 6 Nos. WHPTs, additional gas lift (8 Nos. WHPTs), ZW-100 GI & GL and deck extension ZW-90. Also subsea pipeline connecting the WHPTs for WAG development.	Upper Zakum	Planned award : Q3 2010 Finish : Q1 2012
9	Project	P-8151 : Gas Lift Operability Upgrade and Gas Detection System - (Work Package III)	Gas injection project has been commissioned in Dec-2001 using GG-II gas, which contains sour gas. The existing facilities will be contaminated with H2S due to Gas lift and Gas break-through. Since presently the existing facilities are not designed for the sour gas, these facilities are required to be modified in order to avoid personnel exposure to H2S. Package III involves the EPC works for Toxic Gas detection system.	Upper Zakum	Planned Award : Q4 2011 Finish : Q1 2012
10	Project	P-8363 : Fire & Gas detection system at Zirku	ZADCO have carried out a QRA in order to assess and evaluate the effects of loss of containment on its Oil & Gas facilities on Zirku Island. From the findings of this study there was a recommendation to provide adequate F&G detection and alarm system to replace the existing aging system. As a result, ZADCO has initiated this project with the aim of providing Zirku with a new F&G system to increase the level of safety on the facility. FEED and EPC works to be carried out.	Zirku	Planned Award : Q2 2011 Finish : Q4 2012
11	Project	P-8362 :Potable Water & Sewage Treatment Plant at Zirku	Installation of two RO type desalination plants, each with capacity of 1200m3/day to meet acute shortage of potable water and sewage treatment plant at Zirku. EPC works to be carried for this project.	Zirku	FEED Planned Award : Q3 2009 Finish : Q3 2010 EPC Planned Award : Q1 2011 Finish : Q2 2013
12	Project	P-8361 :Sixth New Winning Pump & Back up header	In order to improve overall reliability and availability to meet cooling water demand in future & post GTP expansion phase-1, the sixth winning pump to be installed. It is proposed to install a new discharge back-up header suitable for future capacity.	Upper Zakum	FEED Planned Award : Q2 2009 Finish : Q2 2010 EPC Planned Award : Q1 2010 Finish : Q4 2012
13	Project	ACPT-2 Floor Repair & ACPT 1 & 2 Dormitory Conversion - EPC	There are leakage problems at all floors of ACPT-2, this has wet the floor covering material (fire retardant insulation). The existing sanitary rooms are found to be the leakage sources, these are required to be demolished completely and re-built, in order to	Upper Zakum	Planned Award : Q3 2009 Finish : Q4 2011
14	Project	P 8374 - Power upgrade at ZIRKU	Installation of additional power generation facilities at Zirku Island since the existing power generation facilities enhancement due to the operational constraints for maintenance of aging turbines, increase in demand for the future projects and improve flexibility of operations	Zirku	FEED Planned Award : Q3 2009 Finish : Q1 2011 EPC Planned Award : Q4 2010 Finish : Q1 2014